

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/10/05

CORNER DESIGNATION: 5N35, V-19, The South Quarter Corner of Section 26.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1 S26
4 S35
2005
PLS 1106

MONUMENT SET:

I re-established this corner by single proportion measurement between the Southeast and Southwest corners of Section 26, holding the Easterly projection of a old fence to the West for latitude. There are also nearby remains of a old down fence, both West and East of the corner point. At the re-established corner position, set a 5/8" x 30" iron rebar with a 1 1/2" aluminum cap, 8" below road surface, cap marked as shown in Monument Marking Detail.

From which:

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level bears North 62° East, 43.5 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level bears South 43° East, 61.6 feet.

A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level bears South 24° West, 36.9 feet.

A 2 3/8" diameter steel fence corner post bears North 34° West, 18.7 feet.

Attached bearing object signs to rebar accessories. Set steel fence post with "witness" sign attached, 8 feet West of corner.

LOCATION AND COMMENTS: Corner is set at a point 2 feet East of West edge of Blue Mountain Station Road. Corner falls in an area of road fill with large rocks, brass cap would not be practical.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 811778.30
E = 8736455.47



FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35V19



Renews 6/30/06

05-112-C