

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/08/05

CORNER DESIGNATION: 5N35, V-23, The South Quarter Corner of Section 25.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake; dug pits; raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1 S25  
4 S36  
2005  
PLS 1106

**MONUMENT SET:**

Corner was re-established by single proportion measurement between the Northeast and Northwest corners of Section 36. At re-established corner position, which falls about 3 feet South of the centerline of Blue Mountain Station Road, set a 3 1/2" brass disk in concrete, 12" below road surface. Cap marked as shown in Monument Marking Detail.

**New accessories:**

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", cap 2" above ground level, bears North 44° East, 24.0 feet.

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", cap 2" above ground level, bears North 69° East, 45.0 feet.

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", cap 2" above ground level, bears South 82° West, 121.4 feet. Set steel fence post with "witness" sign 1 foot from this accessory.

A 5/8" x 24" rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", cap 2" above ground level, bears North 46° West, 28.0 feet.

Attached bearing object signs to all rebar accessories.

LOCATION AND COMMENTS: Corner falls in Blue Mountain Station Road 3' South of road centerline.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 811790.00  
E = 8741654.99



FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Brian Cole

/5N35V23



Renews 6/30/06