

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/21/05

CORNER DESIGNATION: 5N35, V-03, The South Quarter Corner of Section 30.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

Record of Private Surveys, Survey No. 286, calls for "the 1/4 Sec. corner bet Secs. 30 & 31", as being recovered.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1 S30  
4 S31  
2005  
PLS 1106

**MONUMENT SET:**

Corner falls in wheat field with no nearby features. I re-established this corner by single proportionate measurement between the Southwest and Southeast corners of Section 30, using the Odell and Lewis record. I considered applying the record dimension per Survey No. 286, from the Southeast corner of Section 30, but Survey No. 286 only measured the East half of the South line of Section 30. At the re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 16" below ground, marked as shown in Monument Marking Detail. New accessories:

- A silver deep-1 magnet buried 20" below ground level, bears North 24 1/2° East, 50.3 feet.
  - A purple deep-1 magnet buried 20" below ground level, bears South 66 1/2° East, 57.9 feet.
  - A blue deep-1 magnet buried 20" below ground level, bears South 09 1/2° West, 50.5 feet.
  - An orange deep-1 magnet buried 20" below ground level, bears North 60 1/4° West, 41.5 feet.
- Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Corner falls in a farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 811654.79  
E = 8714893.91

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/5N35V03

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6/30/06*

*05-112-c*