

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/01/05

CORNER DESIGNATION: 5N35, V-05, The Southeast Corner of Section 30.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 29, 30, 31 & 32.

Record of Private Surveys, Survey No. 286, did not recover this corner and re-established it. Record states: "set stone cor. for Secs. 29, 30, 31 & 32".

MONUMENT AND ACCESSORIES FOUND: Found set 28" x 18" x 6" stone with 2 drill holes in top and marked "CP" on North face per Record of Private Survey No. 286.

MONUMENT MARKING DETAIL:

T5N R35E
S30 | S29
S31 | S32
2005
PLS 1106

MONUMENT SET: At position of found stone set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe protruding 4" above ground level, marked as shown in Monument Marking Detail. Placed found stone on North side of brass cap monument.

New accessories:

A 5/8" x 30" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level in fence line bears North 16° East, 56.9 feet.

A 5/8" x 30" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level in fence line bears North 30° East, 38.0 feet.

A 3/4" brass washer stamped "PLS 1106" 1.0 feet above ground level in fence corner post bears South 84° East, 23.4 feet.

A 5/8" x 30" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level in fence line bears South 31° East, 47.2 feet.

Attached bearing object signs to all accessories. Set steel fence post 1 foot West of monument with "witness" sign.

LOCATION AND COMMENTS: Corner is approximately 25 feet West of a fence corner with fences North 06° West, East and South 06° East. Corner is East of Pine Creek and West about 75 feet from a old North-South road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 811762.97

E = 8717252.89

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35NV05

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-c