

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/15/05

CORNER DESIGNATION: 5N35, X-09, The East Quarter Corner of Section 32.

## PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

Record of Private Surveys, Survey No. 106, J.W. Kimbrell states "to stone set by P. Zahner for 1/4 sec. cor. bet Secs. 32 and 33", . Kimbrell was running West from the East 1/4 Corner of Section 33. Kimbrell's notes indicate this stone was 3.85 chains or 254.1' West of South end of an old fence which ran N 14° W to the Northwest corner of Section 33. Kimbrell then runs from the Northwest Corner of Section 33, S 12°45' E along the old fence to the South end of the old fence, then continues S 12°45' E to the South line of the Section—he does not call the Southerly corner. There are discrepancies in Kimbrell's notes in this area. There are no remaining fences now. Zahner's Survey is recorded in Record of Private Surveys, Book 1, pages 133 & 134, dated 1885. It appears Kimbrell's Survey No. 106, in 1899, supercedes Zahners

## MONUMENT AND ACCESSORIES FOUND:

I held the intersection of old field berms East, West and North as the best remaining evidence of the original corner location. There is a 22" x 8 x 6" stone lying on the ground here, with no marks. Also is a 2" x 2" square stake 4 feet high. Approximately 237.6 feet East of the re-established corner point is a 4 inch bent metal post in East-West field berm. We probed an dug around the 4 inch metal post but found nothing. The field berms in this area are old, evidenced by built up soil along the berms. I believe the stone and field berms perpetuate the original location of the Odell & Lewis corner, which was "stubbed" South from the Northwest corner of Section 33, and not recovered by either Zahner or Kimbrell.

## MONUMENT MARKING DETAIL:

T5N R35E

1/4

S32 | S33

2005

PLS 1106

## MONUMENT SET:

At the accepted corner position, set a 2 1/2" brass cap on 2 1/2" x 30" galvanized iron pipe, 30" in the ground with cap at ground level, marked as shown in Monument Marking Detail. Found stone is buried North of the new monument.

## New accessories:

The top centerline of a 4" steel pipe, bent West, in an East-West field line bears South 88° East, 237.6 feet.

A blue deep-1 magnet bears South 06° West, 39.2 feet, buried 20" below ground level.

An orange deep-1 magnet bears North 86° West, 26.7 feet, buried 20" below ground level.

An orange deep-1 magnet bears North 58° West, 45.5 feet, buried 20" below ground level.

Buried bearing object signs with deep-1 magnets. Set steel fence post 1.5' East of corner and attached "witness" sign.

LOCATION AND COMMENTS: Corner falls in a actively farmed field.

## OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 809059.53

E = 8722623.88

FIRM: William R. Wells, PLS

P.O. Box 1696



Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witness: Brian Cole

/5N35X09

Surveyor's Seal



Renews 6/30/06

05-112-C