

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/27/05

CORNER DESIGNATION: 5N35, Z-11, The South Quarter Corner of Section 33.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set Standard Cor. for 1/4 Sec. on level; drove charred stake, dug pits and raised mound as per instructions.

In Record of Private Surveys, a unnumbered Survey in Book 1, pages 133 & 134, in 1885, Peter Zahner recovers unmistakable evidence of the corner and renews it by planting a rock 3 x 10 x 15" with a plate underneath it.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

SC
T5N R35E
1/4 S33
2005
PLS 1106

MONUMENT SET:

I held the centerline of East-West Watts Road with the projected intersection of a fence corner and field berm extending North as the best remaining evidence of the original corner location. See Survey No. 02-021-C for additional information. At re-established corner position, set a 2 1/2" brass cap on a 1 1/4 by 30" galvanized iron pipe with cap 12" below gravel road surface, marked as shown in Monument Marking Detail.

New accessories:

- A 3/4" brass washer stamped "PLS 1106" located 1.0 foot above ground level in PP&L power pole #335003, bears North 07° West, 26.6 feet.
 - A 5/8" x 24" rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap flush with ground bears South 80° East, 70.2 feet.
 - A 5/8" x 24" rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap flush with ground bears South 79° West, 52.4 feet.
 - A 3/4" brass washer stamped "OR PLS 1106", located 1.0 foot above ground level in PP&L guy pole #335001 bears North 53° West, 47.9 feet.
- Attached bearing object signs to all accessories. Attached "witness" sign to PP&L pole #335003.

LOCATION AND COMMENTS: Corner is located in centerline of Watts Road. A field line extends North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 806471.02
E = 8725915.36

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35NZ11

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-C