

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/03/05

CORNER DESIGNATION: 5N35, Z-19, The South Quarter Corner of Section 35.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Standard Cor. for 1/4 Sec. on ridge; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

SC
T5N R35E
1 S35
4
2005
PLS 1106

MONUMENT SET:

I held an old East-West fence line for latitude and the original call of 0.50 chains East from a branch of Dry Creek for departure. The main channel of Dry Creek is in a deep channel 33.0 feet East of the re-established corner point. The Easterly branch of Dry Creek, called in the original notes was a overflow channel and does not now exist. At the re-established corner point, set a 2 1/2" brass cap on a 2 1/2" by 30" galvanized iron pipe, 29" in the ground. Cap marked as shown in Monument Marking Detail.

New accessories:

- A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set flush with ground, bears East, 12.7 feet.
 - A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set flush with ground, bears East, 44.6 feet.
 - A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set flush with ground, bears South 60° East, 35.1 feet.
 - A 5/8" x 24" iron rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set flush with ground, bears South 13° West, 33.9 feet.
- Attached bearing object signs to rebar accessories.

LOCATION AND COMMENTS: Corner is in fence line running East-West. Corner is located 8 feet East of a fence corner with fences East and Southerly along Dry Creek. There is a residence Southeast of the Corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 806404.41
E = 8736490.97

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35Z19

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 24, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06