

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/01/05

CORNER DESIGNATION: 5N35, Z-23, The South Quarter Corner of Section 36.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Standard Cor. for 1/4 Sec. on ridge; drove charred stake, dug pits and raised mound as per instructions.

The corner was not recovered on Record of Private Surveys, Survey No. 194, by Geary Kimbrell.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

SC
T5N R35E
1/4 S36
2005
PLS 1106

MONUMENT SET:

I re-established this corner on the parallel of latitude by single proportion measurement, between the Southeast and Southwest corners of Section 36. At the re-established corner position, set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe with cap 20" below ground level, marked as shown on Monument Marking Detail.

New accessories:

- A silver deep-1 magnet buried 20" in ground bears North 39° East, 37.8 feet.
 - A purple deep-1 magnet buried 20" in ground bears South 49° East, 38.5 feet.
 - A blue deep-1 magnet buried 20" in ground bears South 39° West, 43.2 feet.
 - An orange deep-1 magnet buried 20" in ground bears North 51° West, 41.8 feet.
- Buried bearing object signs with deep-1 magnets.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet;

N = 806429.77
E = 8741767.93

LOCATION AND COMMENTS: Corner is 12 feet South of an East-West field line, and in a farmed field. There are no nearby features.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35Z23

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06