

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/03/05

CORNER DESIGNATION: 5N35, Z-25, The Southeast Corner of Section 36.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set Standard Cor. for Secs. 36 & 31, in T 5 N R 35 & 36 E. on side hill sloping to the N.; drove charred stake, dug pits and raised mound as per instructions. This corner and the closing corner to Sections 1 and 6, T4N., R35E., W.M., were recovered on Record of Private Surveys, Survey No. 11, by J.C Arnold, in 1885. The closing corner was re-monumented with a 27 x 10 x 8" stone in the center of N-S traveled lane. In this survey, the relationship between the closing corner and the Standard Southeast Corner of Section 36, T5N., R35E., W.M., was documented by J.C Arnold.

MONUMENT AND ACCESSORIES FOUND: None.

## MONUMENT MARKING DETAIL:

SC  
T5N  
R35E R36E  
S36 | S31  
2005  
PLS 1106

## MONUMENT SET:

The corner area falls in a farmed wheat field, just South of a drainage. I used Survey No. 11, to re-establish the position for the closing corner between Sections 1 and 6, then used the calls in Survey No. 11 to calculate the position for the Standard Southeast Corner common to Sections 36 and 31. See Sheet 2 of 2 of Record of Survey for details on measurements used. At the re-established corner position, set a 2 1/2" brass cap on a 2 1/2" by 30" galvanized iron pipe with cap 20" below ground in farmed field, marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level at South edge of gulch, bears North 42 1/2° East, 30.5 feet.

A purple deep-1 magnet, buried 20" below ground level, in farmed field, bears South 28° East, 33.2 feet.

A blue deep-1 magnet, buried 20" below ground level, in farmed field, bears South 52 1/2° West, 32.3 feet.

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1" above ground level at South edge of gulch, bears North 38° West, 40.3 feet. Buried bearing object signs with the deep-1 magnets. Attached bearing object signs to the rebar accessories.

LOCATION AND COMMENTS: Corner monument is approximately 20 feet South of a small gulch, in a farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 806516.46

E = 8744410.14



FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Brian Cole

/5N35Z25

Surveyor's Seal



Renews 6/30/06

05-112-C