

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/09/08

CORNER DESIGNATION: Z-17, The Southeast Corner of Section 34, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. For Secs. 2, 3, 34 & 35. Drove charred stake; dug pits & raised mound, as per instructions. J.C. Arnold reports finding a stone for the corner, "in the mouth of a lane North", during his survey for County Road No. 299, in 1887. John Kimbrell reports recovering the corner in survey recorded at Book 1, Page 401, Record of Private Surveys. Kimbrell does not state what was found. Steve Haddock searched for this corner during his Survey No. 08-039-C. Haddock calculated a position for the corner based on the Arnold record.

MONUMENT AND ACCESSORIES FOUND: None. There were 2 loose but unmarked stones in the old road bed near the reestablished corner point.

MONUMENT MARKING DETAIL:

T6N R36E

S34|S35

S3 | S2

T5N

2008

PLS 1106

MONUMENT SET: I located this corner with reference to Survey No. 08-039-C and Arnold's record and staked it out on the ground. The corner position is in harmony with the J.C. Arnold record, portions of old fence line extending South about 1/4 mile, and old fence on East side of the lane extending North. At the corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap set flush with ground surrounded by a mound of earth and stone, marked as shown in "Monument Marking Detail".

New accessories:

A 3/4" brass washer stamped "PLS 1106" nailed in South side of 12" branch of a multi-trunk locust bears North 26 1/2° East, 47.8 feet.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 44° East, 14.2 feet.

A 3/4" brass washer stamped "PLS 1106" nailed to North side of a power pole 1 foot above ground level bears South 42° West, 15.6 feet.

A 3/4" brass washer stamped "PLS 1106" nailed to the Southeast side of a 12" locust, 1 foot above ground level bears North 52 1/2° West, 38.1 feet.

Set steel fence post East of corner with witness sign. Bearing object signs are attached to the rebar accessories and accessory trees.

LOCATION AND COMMENTS: Corner falls in centerline of old road or lane extending North and West. There are old fences on each side of the old lane extending North. The portion of the old road extending West is County Road No. 299. There is an old fence line extending South beginning about 100 feet South of corner. Mr. Larry Bishop owns land East of the corner. The land has been in his family for generations. Mr. Bishop contacted me and indicate he believed, and was told by his grandfather, the lane extending North was completely in Section 35. I reevaluated the corner position and supporting record notes, discussed the situation with Mr. Dave Casper, (landowner to the West), and furnished details of the corner position to Dave Krumbein, County Surveyor. Dave Krumbein agreed with my corner position. I also discussed the situation with Gary Roberts, County Road Surveyor.

The result of the reevaluation indicates the corner point is in the proper position, determined from the record references, and I personally informed Larry Bishop of the results of the reevaluation. Based on discussions with Larry Bishop, I do conclude most of the lane and road extending North

09-10-C

are in Section 35, and I positioned the one-quarter corner between Sections 34 and 35 on a straight line between the Southeast and Northeast corners of Section 34. Discussion with Gary Roberts revealed that portions of the road extending North have been assumed to be a County Road, (Hood Road), but road records do not exist creating certain portions of Hood Road.

Our reevaluation of the corner and corner area included extensively probing the old dirt roadbed in the corner area, for buried stones, and searching for the pipe monuments on the South line of Section 34, established by Kimbrell, relative to the corner . Nothing was recovered.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 839440.81

E = 8764692.19

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36Z17



William R. Wells



Expires 6-30-10