

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: May 20, 1998

CORNER DESIGNATION: C-25, East Quarter Corner of Section 1, Township 5 South, Range 30 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by George S. Pershin, under Contract No. 373, dated September 17, 1880. Record states: Set a basalt stone 24 x 14 x 12 in. on E. slope in small open prairie in mound of stone for 1/4 Sec.

MONUMENT AND ACCESSORIES FOUND:
Found stone of record size marked "1/4" on East side of 2 1/2' diameter mound of stone.

MONUMENT MARKING DETAIL:

T5S
R30E R31E
1/4
S1|S6
1998
PLS 1106

MONUMENT SET:

Set at position of found original stone, a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe 20" in the ground and surrounded with a mound of earth and stone. Original stone buried in South side of new mound. Set a steel fence post North of corner and attached witness corner sign.

New Accessories:

A 16" ponderosa pine bears N 20 1/2° E, 174.2 feet scribed "1/4 S6 BT" on double blaze.
A 6" ponderosa pine bears S 31 1/2° E, 115.9 feet scribed "1/4 S6 BT" on double blaze.
A blue "Deep 1" bears S 48 1/2° W, 31.5 feet buried 12" into the ground to bed rock.
A 6" ponderosa pine bears N 71° W, 183.4 feet scribed "1/4 S1 BT" on double blaze.
Tagged bearing trees with bearing object signs.
Placed bearing object sign under ground on North side of "Deep 1", magnetic marker.

LOCATION AND COMMENTS: 1956 Pilot Rock Lumber location poster in old fence jack identifies corner, (S37°E 36 Lks from corner). Corner is 22 feet West of North-South fence.

"Deep 1" refers to magnetic locator marker manufactured by Bernsten, Inc.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: William R. Wells, PLS 1106
John Linder, LSIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-98

RECEIVED BY

Umatilla County Surveyor

Date 5-98
Rec'd by KR
No. 98-104-B