


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-21

History of original corner establishment:

Frank W. Campbell under G.L.O. contract number 468, dated April 12, 1883, set a basalt stone 15"x 10"x 8" marked "1/4" on the west face. He dug pits 18"x 18"x 12" N. & S. of the corner and raised a mound of earth alongside the corner. He marked a BT:



A Pine, 5" dia., S78°W, 222 lks..

Duane Griffith, PLS 644, in 1974 under contract with the Forest Service, found a stone of record size and marked "1/4" in a rock jack 4 ft. NE of the corner point, re-established from the original BT. At the corner point he set a 2 1/2"x 30" iron pipe with a brass cap marked as shown below. From the corner:

The original BT; A Pine, 12" dia., S78°W, 146.5 ft.; with scribing visible. A new BT; A Pine, 12" dia., S21°E, 81.1 ft.; marked: 1/4 S12 T5S R30E BT

Description of corner evidence found:

I found a 2 1/2" iron pipe with a 2 1/2" brass cap marked:

T5S R30E 1/4 S11/S12 1974 PLS 644

From the corner:

A Ponderosa Pine, 15" dia., S79 1/2°W, 146.5 ft.; with healed blaze. A Ponderosa Pine, 16" dia., dead and down, stump bears S18°E, 81.1 ft.; with scribing visible..

Description of monument and accessories I established to perpetuate the original location of this corner:

To maintain the corner I marked a new BT:

A Ponderosa Pine, 11" dia., N50°E, 56.1 ft.; marked 1/4 S12 BT

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs.. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze.. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20°E (per PLS 644)..

May 24, 1989

REGISTERED PROFESSIONAL LAND SURVEYOR

Fayette S. Munro

OREGON JULY 13, 1979 FAYETTE S. MUNRO 1832

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by ..... (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor GPO-788-274

Date 12-89

Rec'd by KA

No. 89-115-A

G-21