


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-7

① History of original corner establishment:

Corner not previously established.



② Description of corner evidence found:

N.A.

③ Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv iron pipe with 3" brass cap 14" in the ground & stamped brass cap as shown on the diagram. Raised a mound of stone around pipe.

From which:

A fir 15" dia. bears N 86 E 7.6 ft. scribed C S 1/16 S8 BT.

A pine 10" dia. bears S 50-45' W 28.4 ft. " " " " "

Set steel posts 5'E & 5'W from corner with bdry & warning signs attached.

Nailed brass washers stamper PLS 848 & bearing tree signs to each tree, painted red band around each tree.

Bearing-Solar Grid.

REGISTERED PROFESSIONAL LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

Witnesses to above corner.

D. Herburger
L. Wyllie

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 26 day of January, 1981
David H. Klaw by _____
(COUNTY OFFICIAL) (DEPUTY)

H-7

S-63-M