


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated 1883. Surveyor General record states: Set basalt stone 15x9x7 ins 10 ins in ground for cor to secs 23, 24, 25&26 mkd with 2 notches on S & 1 notch on E edges from which: A pine 30 ins dia brs S12°W 88 lks. dist. marked T5S R30E S26 BT A pine 30 ins dia brs S28½°E 193 lks. dist. marked T5S R30E S25 BT No other trees within limits and raised mound of stone alongside Corner remonumented by BLM in 1978. BLM notes state: The cor of secs 23, 24, 25 and 26, determined at record bearing and distance from the remains of the original bearing tree: A sawed pine stump 32 ins diam bears S28½°E, 193 lks dist with scribes visible on open blaze with pine log alongside 32 ins diam with scribes visible on open blaze. At the corner point: Set an iron post 28 ins long 2½ ins diam 6 ins in the ground and in a mound of stone 3 ft. base to top with brass cap marked (shown below) from which new bearing trees: A ponderosa pine 11 ins diam bears N9°E, 63 lks dist mkd T5S R30E S24 BT. A ponderosa pine 15 ins diam bears S14°E, 125 lks dist mkd T5S R30E S25 BT. A ponderosa pine 9 ins diam bears S85°W, 73 lks dist mkd T5S R30E S23 BT. A ponderosa pine 11 ins diam bears N69½°W, 121 lks dist mkd T5S R30E S23 BT. Corner is located N16°W, 34 lks from fence corner fences extend N, S, and W. No record of subsequent monumentation found in Umatilla County survey records.



Description of corner evidence found:

Found a 2½" standard BLM brass cap monument marked as shown in small mound of stone.
ORIGINAL BT
Found 32" diameter Ponderosa Pine stump S28½°E 193 lks with scribes visible (tree down alongside with scribes visible)
BLM BTS
Found a 13" diameter Ponderosa Pine N9°E, 63 lks, live and vigorous with blaze evident.
Found a 18" diameter Ponderosa Pine S14°E, 125 lks, live and vigorous with blaze evident.
Found a 10" diameter Ponderosa Pine S85°W, 73 lks, live and vigorous with blaze evident.
Found a 12" diameter Ponderosa Pine N69½°W, 121 lks, dead and standing with blaze evident.
Distances to existing BTs are to the center of the tree

T5S R30E	
S 23	S 24
S 26	S 25
1978	

Description of monument and accessories I established to perpetuate the

original location of this corner: From the above described BLM brass cap monument:

New Bearing Object

A 1/2"x24" iron pin with plastic cap marked "BGA MARKER" bears N8°W, 41.20 feet and is set at the North end of a gate on an existing North-South fenceline.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary sign attached.

Rebuilt mound of stone around monument, 3 ft. base to top of cap.

I hereby certify that the above corner point was perpetuated as hereon described on May 6, 1989.

Witnesses: Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new bearing object. I used 17° East magnetic declination and the distance is to the center of the plastic cap on the pin.

Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 28th day of June, 1989
David W. Keams by Kathleen Ambrose
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71) Umatilla County Surveyor

☆ U.S. GOVERNMENT PRINTING OFFICE - 1963-793-276

Date 6-89
 Rec'd by KA
 No. 89-61-R