


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated 1883. Surveyor General record states: Set basalt stone 15x12x8 ins 8 ins in ground for cor to secs 25, 26, 35&36 marked with 1 notch on S&E edges from which:  
 A pine 20 ins dia brs S18°E 102 lks. dist. marked T5S R30E S36 BT  
 A pine 10 ins dia brs S58°W 106 lks. dist. marked T5S R30E S35 BT  
 A pine 30 ins dia brs N64°W 69 lks. dist. marked T5S R30E S26 BT  
 A pine 30 ins dia brs N70°E 67 lks. dist. marked T5S R30E S25 BT  
 Corner remonumented by BLM in 1978. BLM notes state: The cor of secs 25, 26, 35 and 36, monumented with the original unmarked basalt stone, 15x12x8 ins, firmly set 2 ins in the ground and in a mound of stone from which the original bearing trees: A pine 26 ins diam bears N70°E, 67 lks dist with scribes visible on open blaze. A pine 26 ins diam bears S18°E 104 lks dist with scribes visible on open blaze (record 102 lks). A pine 12 ins diam bears S58°W 106 lks dist with scribes visible on open blaze. A root hole bears N64°W 69 lks dist with a down and decayed pine alongside, no marks visible. At the corner point: Set an iron post 28 ins long 2½ ins diam 15 ins in the ground and in a mound of stone 3 ft. base to top with brass cap marked (shown below) from which a new bearing tree: A pine 14 ins diam bears N55°W, 34 lks dist mkd T5S R30E S26 BT. Deposit corner stone alongside iron post. No record of subsequent monumentation found in Umatilla County survey records.



Found a 2½" standard BLM brass cap monument marked as shown in mound of stone.

Found original and BLM bearing trees as described in the BLM record above. Distances to existing BTs are to the center of the tree

T5S R30E  
 S 26 | S 25  
 S 35 | S 36  
 1978

Description of monument and accessories I established to perpetuate the original location of this corner:

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet South with land survey monument and property boundary sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on May 8, 1989.

Witnesses: Rick Robinson and Jeff Petersen.



Office of Surveyor County of Umatilla  
 State of OR, I hereby certify that the within instrument was filed in this office for record on the 28<sup>th</sup> day of June, 1989  
David H. Kumberein by Kathleen K. Kumberein  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 6-89  
 Rec'd by KA  
 No. 89-63-89

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

V-21