

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


1-20

History of original corner establishment: Corner established in 1880
by George S. Pershin, under Contract No. 373.

Surveyor General Record States:

Set a basalt stone 20x14x8 on slight NW slope for 1/4 sec. cor.:

A pine 22 in. in diam. brs. East 68 lks. dist.
A pine 36 in. in diam. brs. S. 48° W. 58 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

I did not find the original 1/4 corner stone. I establish this corner at record bearing and distance from the one remaining BT. From the corner point:

A 40" pine bears S. 48° W. 38.3 ft. mkd. 1/4 S BT, in blaze that has been opened years ago.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the corner points: Set a 2 1/2"x30" galvanized iron pipe 14" in the ground marked as shown: From which I scribe one NEW BEARING TREE:

A 20" pine bears S. 70° E. 141.6 ft. mkd. T5S R31E 1/4 S31 BT.


I nailed a brass washer marked "OPLS 598" to the BT blaze of this tree. Set a steel fence post 5 ft. N. of corner. Raised a mound of stone, 3 ft. base to top of pipe. Corner is at the SE corner of a stock water pond. Used a compass with 20° E. variation and steel tape, measuring to center of BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Bagett

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

Sept. 30, 1976



Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

I-104-R

x-25