

USDA-FOREST SERVICE

Index

File No. Z-17

TSS

R30E

R.D.

CORNER RECORD (SEARCH)

Tract or

Cor.

Merid. Willamette

N.F.

Ref. FSM 7151.4

Survey No

No.

North Fork John Day

County Umatilla

Umatilla

State

Oregon

x

1

1

Corner Diagram

SC

1 Describe corner monument found

T5S R30E

1 Steel pipe extending 18" above ground with 2 1/2" brass cap stamped as shown in the diagram. Monument was pushed over in the remains of a stone mound.

S34 | S35

1

T6SR30E52

1

1976

1

OPLS 598

1

x

1

x

Photo Identification Data

1 Describe bearing trees or other official accessories found

Photo No.

1 A 24" Ponderosa Pine bears N42°E, 119.7' with healed scribe.

filed at

1 A 9" Ponderosa Pine bears N62°W, 93.9' with healed scribe.

Object Ident.

1

Ident. by

1

Signature

1

x

1

x

Plane Coordinate Position Data

1 Describe corner location relative to near-by features, also how to reach corner

State

Zone

1 From the junction of roads 5312 and 5320, follow 5320 east 1.6 miles to road

X

1 5320110. Then follow road 5320110 east 1.4 miles and follow a logging spur road

Y

1 south through an open area to a east-west fence. The corner lies in the opening

Estab. by

1 approximately 50' east from where the logging spur goes through the fence.

Agency

1

x

1

x

Signature

Title

Division

Headquarters

Date

7100.52

*David L. Haddock*

Land Surveyor

Pendleton, OR

June 1988

CORNER RECORD (PERPETUATION)

X-----X

Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' west of the monument and attached Forest Service Land Survey Monument and Property Boundary signs. Set monument back in place and replaced stone mound around monument.

X-----X

Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Repainted red bands around trees. Attached Forest Service Land Survey Monument signs to trees.

X-----X

Work done by	David L. Haddock	Title	Land Surveyor	Date	Nov 1989	State Registration No.	
Certified cor. record prepared?	yes		no x	Filed at		or Agency	852
						Date	

X-----X

REMARKS

X-----X

Index File No.    7-17    T.55.    R.30E.    M. Willamette    Tract or Survey No    Cor.

USDA-FOREST SERVICE

Index  
File No. Z-17  
T 55 R. 30E  
Merid. WILLAMETTE

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_  
Cor. No. SEC

Z-17

R.D. UKIAH County UMATILLA  
N.F. UMATILLA State OR

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

FOUND BASALT STONE 15" x 9" x 5" SET IN MOUND OF STONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
Signature \_\_\_\_\_

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

COR IS 150 FT SOUTH OF OLD RD.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
Agency \_\_\_\_\_

Signature

*R.D. B... ..*

Title

LAND SURVEYOR

Division

Headquarters

Date

9-30-76

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

SET 2 1/2" x 30" IRON PIPE WITH BRASS CAP MKD

SC  
T55R30E

S34 | S35  
T65R30E S2  
1976

OPL548

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 2" PINE BRS N42°E 119 1/2 FT. MKD T55R30E S35 SC BT.  
A 9" " " N62°W 193 1/2 " " T55R30E S34 SC BT.

Work Done By: R.D. ROGETT Title: LAND SURVEYOR Date: 9-30-76 State Registration No. OPL548  
or Agency: OPL548

Certified Cor. Record Prepared? Yes  No  Filed At: UMATILLA CS Date \_\_\_\_\_

REMARKS