


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by George S. Pershin under GLO contract number 361, dated August 2, 1880. Surveyor General record states: Set basalt stone 20x8x4 on S.E. side of rocky point for cor. to sec. 35 and sec. 36. Fir 16 in. di. brs. N44°E 50 lks dist. No tree in N.W. raised mound of stone around corner.



Corner remonumented by David H. Krumbein, OPLS 933, in 1977. His record states: Description of corner evidence found: NONE. Set a 2½" x 30" iron pipe 19" in the ground with brass cap marked as shown (labeled "record" below): from which I scribed new Bearing Trees.

A 8" pine bears N. 08° 45' E. 66.73 ft. marked T. 5 S., R. 30 E., S. 35 SC BT
 A 14" fir bears N. 64° 33' E. 76.32 ft. marked T. 5 S., R. 30 E., S. 36 SC BT

No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a 2½" brass cap monument marked as shown (labeled actual) in mound of stone.

Found a 14 inch diameter Douglas Fir N64°E, 76.3 ft., sickly with scribes visible.

Found a 12 inch diameter Ponderosa Pine N9°E, 66.7 ft. live and vigorous with scribes visible.

Found a 3/4" diameter iron pipe approximately 30 feet East (Appears to be a flight control.)

Distances to existing BTs are to the center of the tree

RECORD
 T 5 S R 30 E
 SC
 S 35 S 36

 T 6 S R 30 E
 1977
 PLS 933

ACTUAL
 T 5 S R 30 E
 SC
 3 3
 T 6 S R 30 E
 1977
 PLS 933

Description of monument and accessories I established to perpetuate the original location of this corner: From the existing found brass cap monument, I take a new Bearing Object as follows:

New Bearing object:
 A cliff 20 feet high and 60 feet long running northeast-southwest bears N33°E, 47.7 feet marked X B0 near the center approximately 2 feet above the base of the cliff.

Painted a 6 inch red band around all BTs and B0s and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on May 9, 1989.

Witnesses: Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new bearing object. I used 17° East magnetic declination and the distance is to a the chiseled "X" on the bearing object.

Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 28th day of June, 1989
David H. Krumbein by Kathleen K. Amberg
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71) Umatilla County Surveyor

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

1-4
 Date 6-89
 Rec'd By KA
 No. 89-45-R

Z-21