


History of original corner establishment: Corner established in 1880 by George S. Pershin, under Contract No. 362.

Surveyor General Record States:

80.00 set basalt stone 17x12x6 on south face of bluff for corner to T5S R30 and 31 E.:

A pine 8 in. in diam. brs N. 48° W. 107 lks. dist.
A pine 22 in. in diam. brs N. 71° E. 128 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

Found stone 6"x12"x17" set in a mound of stone, no mks visible. Set on South face of bluff. From which:

A dead and down 23" pine bears N. 71° E. 70.6 ft. mkd T5S R31E S31 SC BT (Orig. BT)
No evidence of the other BT was found.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point: Set a 2 1/2"x30" iron pipe 18" in the ground. From which I scribe NEW BEARING TREES:

A 31" pine brs. N. 30° E. 141.0 ft. mkd T5S R31E S31 SC BT.
An 18" pine brs. N. 47° W. 95.4 ft. mkd T5S R30E S36 SC BT.


I nailed a brass washer mkd "OPLS 598" to the BT blaze of both trees. Set a steel fence post 5 ft. North of corner. Buried original corner stone west and alongside iron pipe. Raised a mound of stone 3' base to top of pipe. Corner is 200 ft. North of Five Mile Creek road. Used compass with 20° East variation and steel tape, measuring to center of BTs.

REGISTERED PROFESSIONAL LAND SURVEYOR

Robert D. Bagett

OREGON
JULY 12, 1903
ROBERT D. BAGETT
598

Sept. 30, 1976



Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)