


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1880 by George S. Pershin under General Land Office Contract No. 373.

Surveyor General Records States:

Set basalt stone 17 x 8 x 7 ins. for cor. to sect's 7-18-12-13.

- A 12" Pine bears N 56 E, 167 lks.
- a 10" Pine bears S 42 E, 28 lks.
- A 26" Pine bears S 38 W, 116 lks.
- A 28" Pine bears N 62 W, 210 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:  
Found mound of stone, from which:

Original BTs

- A 18" Pine, good condition, bears S39E, 18.5 ft., blaze healed. North-South fence attached to this tree.
- A 27" Pine, good condition, bears S42W, 76.6 ft., scribes visable.

No evidence of other BTs and could not identify original marked stone.


Description of monument and accessories established to perpetuate the original location of this corner

At corner point, based on original BTs, I set 2½"x30" iron pipe with brass cap, marked as shown, 24" in ground, from which:

New BTs

- A 14" Pine bears N78E, 45.1 ft. marked T5S R31E S7 BT.
- A 10" Pine bears N28W, 31.3 ft. marked T5S R30E S12 BT.

Nailed brass washer to BT blaze.  
Set steel fence post 5+ ft. East of corner  
Raised mound of stone 5 ft. at base to top of cap.  
Used steel tape and magnetic compass with 20° E declination.  
Measured to face of blaze on original BTs and center of new BTs.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 13 day of August, 1974, at 11 o'clock a.m., (signed)  
Ralph Thompson by \_\_\_\_\_ (DEPUTY)

*I-124-R*  
*J-25*