

Index File No. J-11

CORNER RECORD (SEARCH)

Tract or Survey No. _____

Cor. No. J-11

22 15

T 5S R. 31E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

set basalt stone 18x10x5 in open glade on level for $\frac{1}{4}$ sec. cor.

Monumented By BLM in 1978

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

pine 22" dia. bra. N28E 75 lks. dist.

pine 28" dia. brs. S73E 145 lks. dist.

original notes




PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Followed old fence line east from sec. 8-9-16-17, down a slight hill to old logging rd. About 200 yds. below rd. found Form 458 on PP tree. Found pile of rock. Found stump with inscribing on it. We could read some of the inscribing on the notes. Took brng and found Pine snag with inscribing on it. Chained dist. it corresponds with original notes. In company with R. Swainston.

Signature

Title

Division

Headquarters

Date

7100-52

151 U.H. AVERETT

Eng. Aide

3-31-65

REV. 65 5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

9

ACCESSORIES DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

10

Work Done By _____ Title _____ Date _____ State Registration No. or Agency _____

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

11

REMARKS

12

Index File No. J-11 T. R. M. Tract or Surv. No. Cor. 13