


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index No. N-1

History of original corner establishment:

The original notes state that George S. Pershin, under contract No. 373 dated September 17, 1880, set a basalt stone 20" x 12" x 7" on a S. E. Slope from which:

- A pine 22" dia. bears N. 34°E78 LKS (51.5 ft.)
- A pine 24" dia. bears S78°E 63 LKS (41.6 ft.)
- A pine 10" dia. bears S76°W 61 LKS (40.3 ft.)
- A pine 20" dia. bears N57° W 63 LKS (41.6 ft.)



No record of subsequent remonumentation found in County Records .

Description of corner evidence found:

Found a basalt stone 24" x 12" x 7" with no marks. The area has been logged and the stone appears to have been moved (reset from BT).
A 24" pine stump (rotted) with blaze visible but no visible scribing bears N34°E51.5 ft. to center.

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 20 inches in the ground and surrounded with a mound of stones to the cap.
Set steel fence post North of corner and attached sign 54-4.

Established 4 new BT's: A 13" bullpine bears N73½°W 71.2 ft. scribed T55 R30E S13BT.

A 12½" bullpine bears N61½°E43.2 ft. scribed T55 R31E S18BT.

A 9½" bullpine bears S60½°E 44.0 ft. scribed T55 R31E S 19 BT.

A 12" red fir bears S56½° W 80.4 ft. scribed T55 R30E S24 BT.

New BT's have lower blaze scribed BT with a brasswasher stamped PLS 1106 nailed to it.

BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Location poster is placed on North side of road up Wilkens Creek 800± South of Corner.

Used steel tape and magnetic compass with 19½° east declination . Measured to center of Bts.

See map of survey

This corner set July 29, 1979

Witnesses: Greg Flowers LSIT
Brent Reynolds

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla
State of Oregon , I hereby certify that the within instrument was filed in this office
for record on the day of

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date Sept 4, 1979

Rec'd By M. Hughes

No. Q-1164-B