

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/23/02

CORNER DESIGNATION: N-13, The Southwest Corner of Section 15, T5S, R31E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 373, dated September 17, 1880. Notes state: Set basalt stone 16 x 10 x 8 and post in mound of stone in large open glade on N. Slope for cor. To Sec. 15,16,21 & 22. No trees. In 1975 survey of Ukiah-Dale Wayside, Survey No. K-8-B, State Parks surveyors recovered the corner stone and marked three new bearing trees:  
12" pine N 39° E 69.5 ft. scribed "T5SR31ES15BTRS691".  
19" pine N 22° W 147.5 ft. scribed "T5SR31ES16BT".  
13" pine S 21° E 175.5 ft. scribed "T5SR31ES22BT".

MONUMENT AND ACCESSORIES FOUND: Found set 16" x 10" x 8" basalt stone with three notches on East and South sides, in a stone mound, from which:  
A 18" ponderosa pine with scribing visible on partly healed blaze bears S 20° E 175.3', (State Parks BT).  
A 24" ponderosa pine with healed blaze bears N 22° W 147.4', (State Parks BT).

MONUMENT MARKING DETAIL:

T5S R31E  
S16|S15  
-----  
S21|S22  
2002  
PLS 1106

MONUMENT SET:

At position of found stone, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe with cap projecting 6" above the ground. Rebuilt stone mound and buried corner stone on SW side of new monument. Monument marked as shown in "Monument Marking Detail".

New Accessories:

A 18" ponderosa pine bears N 36° E 69.2', scribed T5S R31E S15 BT. Nailed 3/4" brass washer stamped "PLS 1106" to lower part of blaze. (This is also a State Parks BT, the blaze was healed and we did not have State Parks narrative notes when corner was remonumented).  
"XBO" chiseled on top of a 24" x 18" x 6" above ground rock in place bears S 65° W 75.5'. Measured to the chiseled "X" of this accessory.

All accessories except "XBO" rock have bearing object signs attached. Nailed "witness" sign to back side of bearing trees.

LOCATION AND COMMENTS: There is current private logging activity in the area.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD 83/91, INT. FOOT:

N = 536058.91  
E = 8598915.97

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
\\SS31N13

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-04*

RECEIVED BY

Umatilla County Surveyor

Date 10-02

Rec'd By KF

No. 02-218-B