

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 07/18/02

CORNER DESIGNATION: P-17, The East Quarter Corner of Section 22, T5S., R31E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by George S. Pershin, under Contract No. 373, dated Sept. 17, 1880. Notes state: Set basalt stone, 20 x 16 x 8, on N. slope, for 1/4 Sec. Cor. A pine, 28 ins. diam., brs. E., 44 lks. dist. A pine, 36 ins. diam., brs. N.72°W., 70 lks. dist.

MONUMENT AND ACCESSORIES FOUND: Found 24" x 16" x 8" set stone leaning slightly West, marked 1/4 on both top and bottom of East face of stone. Nothing exists for the original bearing tree at N 72° W, 70 links. There is a stump hole East, 44 links, (original bearing tree).

**MONUMENT MARKING DETAIL:**

T5S R31E  
1/4  
S22 | S23  
2002  
PLS 1106

**MONUMENT SET:**

At position of found corner stone set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 4" above ground level and surrounded with a mound of stones and earth, marked as shown in "Monument Marking Detail". Buried original stone on West side of monument in the mound of stone.

**New Accessories:**

A 6" nail in the center top of a 20" diameter pitched ponderosa pine stump, cut 20" above ground level bears N 86 1/2° E, 87.8 feet.

A 6" ponderosa pine scribed: "1/4 S23 BT" with a 3/4" brass washer stamped "PLS 1106" in the "B" of "BT", bears S 42° E, 62.5 feet.

A 4" ponderosa pine with an "X" scribed at breast height and "BT" at base with 3/4" brass washer stamped "PLS 1106" in the "B" of "BT" bears S 31° W, 28.6 feet.

A 6" nail in the top of a 20" diameter pitched ponderosa pine stump cut 23" above ground level bears N 13° W, 80.7 feet.

Attached bearing object signs to all accessories.

LOCATION AND COMMENTS: Corner located in timber about 1/4 mile West of the Ukiah-Granite Road.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD 83/91, INT. FOOT:

N = 533559.43  
E = 8604238.36

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
VS31P17

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

renews 6-30-04 RECEIVED BY

Umatilla County Surveyor

Date 10-02

Rec'd By KK

No. 02-218-B