


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

5-5

History of original corner establishment:

None

Index No. S-3



No record of subsequent remonumentation found in County Records .

Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 18 inches in the ground and surrounded with a mound of stones to the cap .
 Set steel fence post South and East of corner on property line and attached signs 54-2 and 54-9.
 Established 2 new BT's: A 11" red fir bears N54°E 5.9 ft. scribed CN 1/16 S 30 BT.
 A 8½" red fir bears S52½°E 11.6 ft. scribed CN 1/16 S 30 BT.
 BT's have lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.
 BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Used steel tape and magnetic compass with 19½° east declination . Measured to center of Bts.

See map of survey


This corner set August 21, 1979

Witnesses: Greg Flowers L.S.I.T.
 Brent Reynolds

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106



Office of _____ County Surveyor _____ County of Umatilla
Oregon, I hereby certify that the within instrument was filed in this office
 for record on the _____ day of _____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date Sept 4, 1979

Rec'd By M. Hughes

No. Q-1164-B

Form R6-7100-57 (9/71)

NOTE: This corner was erroneously established in 7/79 and bearing trees established. When the corner was established in its true position, scribing and signs were removed from BT's referencing the erroneous position. From the correct corner position: A 11½" red fir bears S86°E 227.± feet with open blaze. A 11" red fir bears S78°E 210± feet with open blaze.