

USDA-FOREST SERVICE

Index T-3  
File No. \_\_\_\_\_  
T 5S R. 31E  
Merid. Willamette


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Sec 30  
Survey No. \_\_\_\_\_  
Cor. C 1/4  
No. \_\_\_\_\_

R.D. Ukiah  
County Umatilla  
N.F. Umatilla  
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner located in the bottom of small canyon on east side of dry stream bed.

Signature *William R. Wells* Title PLS 1106 Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date 8/21/79  
7100-52-(3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set a 2" x 30" galvanized iron pipe, with brass cap 2 1/4 inches in ground with a mound of stone to the cap marked:  
 Set steel fence post on property line North of corner and attached signs 54-2 and 54-1.

T55 R31E  
 C 1/4 S30  
 1979  
 PLS 1106

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A 8" red fir bears S 65°E 9.7 ft. to center C 1/4 S30 B.  
 A 10" red fir bears S8°E 17.1 ft. to center scribed C 1/4 S 30 BT.  
 BT's have a lower blaze scribed BT with a brass washed stamped PLS 1106 nailed flush.  
 Attached signs 54-3 and 54-4 and red ring around BT's.

v  
 Painted a

Work Done By William R. Wells Title PLS Date 8/21/79 State Registration No. 1106  
 or Agency

Certified Cor. Record Prepared ? Yes  No  Filed At: Umatilla County Surveyors Office Date

**REMARKS**

NOTE: This corner was erroneously established in 7/79 and bearing trees established when the corner was established in its true position, scribing and signs were removed from BT's referencing the erroneous position. From the correct corner position:

A 13" red fir bears N 68 1/2°E 177 ± w/open blazes.  
 A 11 1/2" red fir bears N85°E 156' ± w/ open blazes.