

USDA-FOREST SERVICE

Index File No. U-2

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 30

Cor. S W 1/16
No. _____

T 5S R. 31E

R.D. Ukiah


County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



T5S R31E W.M.

DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Located on flat on top of Rocky Ridge in stand of small bull pine.

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature
William R. Wells

Title
PLS 1106

Division

Headquarters

Date
8/11/79

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2" x 30" galvanized iron pipe with a brass cap 9 inches in ground with a mound of stones to the cap marked:
 Set steel fence post on property line North and West of corner and attached signs 54-2 and 54-9.

TSS R31E
 SW 1/16 S30
 1979
 PLS 1106

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set 2 New BT's:
 BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush.
 Attached signs 54-3 and 54-4 and painted red ring around BT's.

10

Work Done By: William R. Wells Title: PLS Date: 8/11/79 State Registration No. 1106
 or Agency: Umatilla County Surveyor's Office
 Certified Cor. Record Prepared? Yes No Filed At: _____ Date: _____

11

REMARKS

This corner was established in error in 7/79 and bearing trees established. When the corner was established in its true position, scribing and signs were removed from 1 BT referencing the erroneous position. From the true corner position:
 A 9" Bullpine bears N 1° E 18.8 feet with open blaze.

Index File No. U-2 T. 5S R. 31E M. Willamette Tract or Surv. No. Sec. 30 Cor. S. W. 1/16
U.S. G.P.O. 1977-725-576/586

12