


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

U-3

History of original corner establishment:

None

Index No. U-3



No record of subsequent remonumentation found in County Records .
Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 22 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence post North and East of corner on property line and attached signs 54-2 and 54-9.

Established 2 new BT's: A 8 1/2" red fir bears N87°E 70.8 ft. scribed CS 1/16 S 30 BT.

A 8 1/2" red fir bears N81° E 69.1 ft. scribed CS 1/16 S 30 BT.

BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.
See map of survey


This corner set August 20, 1979

Witnesses: Greg Flowers L.S.I.T.
Brent Reynolds

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla
State of Oregon I hereby certify that the within Instrument was filed in this office
for record on the day of
..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date Sept 4, 1979

Rec'd By M. Hughes

No. Q-1164-B