

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner position determined by Bureau of Land Management by survey performed during 1967-1980:


Set an iron post, 28 ins. long, 2 1/2" diam., 12 ins. in the ground to solid rock, in a mound of stone, 2 1/2 ft. base to top, with brass cap marked:

SC
W 1/16 S32

From which:

A Pine, 15 ins. diam. bears N57°W 47 lks. dist., mkd. W 1/16 S32 SC Bt.

No other suitable trees within limits in Sec. 32.



Description of corner evidence found:

Found a 2 1/2" dia. iron pipe, firmly set in a mound of stone as described in the BLM Record, with brass cap attached, marked:

U.S. Dept. of The Interior
Bureau of Land Management
SC

From which:

The only BT as marked by BLM, a 15" Ponderosa Pine, alive and well-healed bears N 57°W 30.9 feet.

W 1/16 S32
1968

Description of monument and accessories established to perpetuate the original location of this corner:

We mark a new bearing tree, a 10" Ponderosa Pine, scribed "W 1/16 S32 BT" on a double blaze, bears N 76°E 103.9 ft. Attached brass washer marked "LS 1099" to lower blaze on new BT.

Magnetic Compass (20° East Declination)
Steel Tape

September 7, 1984

Witnesses:

Gary Langlitz, LS 1099
Ray Crapo
Greg Orton



Office of Surveyor..... County of Wasco.....
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 7 day of October, 1984
David Krumbein by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)