

Index
File No. E 13

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. SW Cor. No. Sec. 3

T 5 S R. 34 E R.D. La Grande County Union

Merid. Willamette N.F. Wallowa-Whitman State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND 1

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND 2

Found 42" stump in section 4.
Found 42" stump in section 3.
Found 48" stump in section 9.
Found rock, all half scribes, in section 10.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER 3

Take Tin Trough Road S442

PHOTO IDENTIFICATION DATA 6

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature 7

PLANE COORDINATE POSITION DATA 8


State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature	Title	Division	Headquarters	Date	7100-52 (3/68)
J. G. Voelz	Co. Surveyor		La Grande	8-24-70	5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 30" galvanized pipe with a bronze cap on top.
 The hole was backfilled with stone and tamped soil.
 I stamped the disk.



ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Ponderosa Pine 12" dia, N42°W at a distance of 12.6 ft., scribed T5S R34E S4 BT.
 Ponderosa Pine 14" dia, N8°E at a distance of 26.4 ft., scribed T5S R34E S3 BT.
 Pine 8" dia, S14°W at a distance of 38.1 ft., scribed T5S R34E S9 BT.
 Ponderosa Pine 9" dia, S38°E at a distance of 7.7 ft., scribed T5S R34E S10 BT.
 Placed bearing tree signs on old and new bearing trees and painted stripe
 around the trees. I placed a steel fence post with USFS sign 54-4 attached
 near the corner. Placed the stone along side the monument.

Work Done By J. G. Voelz Title Co. Surveyor Date 1970 State Registration No. Ore Lic 381
 or Agency _____
 Certified Cor. Record Prepared ? Yes No _____ Filed At: La Grande, Oregon Date Sept. 1970

REMARKS