


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner established as part of this survey. Corner was established in 1982 by Curtis D. Moore, Surveyor General Land Office Contract No. 451. Surveyor General's Records states: Set a basic line 17" x 4" x 7" x 12" in ground for 1 sec. cor. marked 1/2 on North side, from which 2 pins 6" dia. bears S 87 W, 6.15; north-south S 87 BT. A pin 6" dia. bears S 82 E, 11.15; dist. marked 19 BT.



Description of corner evidence found:

None. At assumed corner location I found no acceptable evidence of stone as previously described, however I did find the remains and traces of the scribbling S 87 BT on both bearing trees lying on the ground, and could determine the original location of both bearing trees.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by survey... Set a 2 1/2" aluminum cap on 2 1/2" x 30" aluminum pipe 20" in ground surrounded with large stone mound. Set a steel fence post 4' North of corner & attached sign 54-9 & 54-2. 2 1/2" brass cap on a 30" galv. pipe and being stamped as shown above in the ground, with a New bearing trees established: A 13" diam. Western Larch brs. S 78 W, 79.4' scribed C1/4S8 BT. A 8" diam. Douglas fir brs N 08 W, 24.8' scribed C1/4S8 BT. A 9" diam. Western Larch brs. S 86 E, 76.9' scribed C1/4S8 BT. A 15" diam. Douglas fir brs S 25 E, 32.2' scribed C1/4S8 BT. New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

Compass declination 18° East.

I hereby certify that the above corner was properly established to U.S.F.S. standards by me on October 26, 1993.

JAMES H. HANBLETON
C15

REGISTERED PROFESSIONAL LAND SURVEYOR

Will R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
renews 12-31-94

Office of... County Surveyor... County of... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the... day of... 19...

by... (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71) Umatilla County Surveyor

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

Date 8-4-94
Rec'd By RK
No. 94-106-C
4

93-37-B