


Index
File No. G-7
T 5 S R. 34 E
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____
R.D. La Grande County Union
N.F. Wallow-Whitman State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None. Corner established with this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is approx. 225' North of Road 5160-606.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estob. By _____
Agency

Signature
Walt. R. Wells

Title Land Surveyor Division _____

Headquarters Pendleton, OR. Date 10-26-93

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position established by survey...

Set a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe 20" in ground surrounded with large stone mound. Set a steel fence post 4.0' North of corner & attached sign 54-9 & 54-2.

Compass declination 18° East.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 13"diam. Western Larch brs. S78° W, 79.4' scribed C1/4S8 BT.

A 8"diam douglas fir brs N08° W, 24.8' scribed C1/4S8 BT.

A 9"diam. Western Larch brs. S86° E, 76.9' scribed C1/4S8 BT.

A 15" diam douglas fir brs S25° E, 32.2' scribed C1/4S8 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R.Wells Title Land Surveyor Date 10-26-93 State Registration No. PLS 1106 or Agency

Certified Cor. Record Prepared ? Yes ~~XXX~~ Filed At Utah County Surveyor Date 8/94

11

REMARKS

Index File No. G-7 T. 5 S. R34 E. WMM. Tract or Surv. No. Cor. 13