

Index File No. H-8

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_

Cor. No. \_\_\_\_\_

T 5 S R. 34 E

R.D. La Grande County Union

Merid. Willamette

N.W. Wallow-Whitman State Oregon

CORNER DIAGRAM

T 5 S R 34 E

SE 1/16 • S 8

1993

PLS 1106



DESCRIBE CORNER MONUMENT FOUND

None. Corner established as part of this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

Signature

7

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

Agency

8

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 100' South of Road 5160.

Signature

Willi R. Wells

Title

Land Surveyor

Division

Headquarters

Pendleton, OR.

Date

10-28-93

FS-7100-52 (3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position established by survey...

Set a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe 10" in ground surrounded with mound of earth & stone. Set steel fence post 3.8' East of corner & attached sign 54-9 & 54-2.

Compass declination 18° East.

9

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 12" ponderosa pine brs S32°E, 75.4' scribed SE1/16S8 BT.

A 27" ponderosa pine brs N78°W, 138.5' scribed SE1/16S8 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R.Wells Title Land Surveyor Date 10-28-93 State Registration No. PLS 1106 or Agency

Certified Cor. Record Prepared ? Yes ~~XXX~~ Filed At Umatilla County Surveyor Date 8/94

11

REMARKS

Index File No. H-8 T. 5 S R. 34 E WMM. Tract or Surv. No. Cor. 13