


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

L-7

**History of original corner establishment:**

None. Corner established as part of this survey.



**Description of corner evidence found:**

None.

**Description of monument and accessories established to perpetuate the original location of this corner**

At position established by survey...

Set a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe 28" in ground surrounded with mound of earth & stone. Set steel fence post 4.0'South of corner & attached sign 54-9 & 54-2.

**New bearing trees established:**

- A 19"diam.Western Larch brs.S80°E,135.9' scribed C1/4S17 BT.
- A 12"diam douglas fir brs S15°W,58.0' scribed C1/4S17 BT.
- A 8 1/2"diam.Western Larch brs.N84°W,48.0' scribed C1/4S17 BT.
- A 10"diam.Western Larch brs.N46°W,47.1' scribed C1/4S17 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each

Compass declination 18° East.

I hereby certify that the above corner was properly established to U.S.F.S. standards by me on October 28, 1993.

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*Will. R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
---

Office of County Surveyor County of Umatilla *renews 12-31-94*  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the ..... day of .....; 19....., at ..... o'clock .....m., (signed)  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

**RECEIVED BY**

Umatilla County Surveyor

Date 8-4-94

Rec'd By KK

No. 94-106-C

10