

Index
File No. L-7

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 5 S R. 34 E

R.D. La Grande County Union

Merid. willamette

N.F. Wallow-Whitman State Oregon

CORNER DIAGRAM

T 5 S R 34 E

C 1/4 S 17

1993

PLS 1106



DESCRIBE CORNER MONUMENT FOUND

None. Corner established as part of this survey

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is 500' West of Road No. 5160.

Signature

Walter R. Walls

Title

Land Surveyor

Division

Headquarters

Pendleton, OR.

Date

10-28-93

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position established by survey...

Set a 2½" aluminum cap on 2½"x30" aluminum pipe 28" in ground surrounded with mound of earth & stone. Set steel fence post of corner & attached sign 54-9 & 54-2.

Compass declination 18° East.

9

ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 19" diam. Western Larch brs. S80° E, 135.9' scribed C1/4S17 BT.

A 12" diam douglas fir brs S15° W, 58.0' scribed C1/4S17 BT.

A 8½" diam. Western Larch brs. N84° W, 48.0' scribed C1/4S17 BT.

A 10" diam. Western Larch brs. N46° W, 47.1' scribed C1/4S17 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R. Wells Title Land Surveyor Date 10-28-93 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes XXXX Filed At Utah County Surveyor Date 8/94

11

REMARKS

12

Index File No. L-7 T. 5 S R. 34 E WM. M. Tract or Surv. No. Cor. 13