


L-9

History of original corner establishment:

Corner was established in 1882, by Rufus S. Moore, under Gernerl Land Office Contract No. 451. Surveyor General's records state: Set a basalt stone 16" x 12" x 8", 11" in ground for the 1/4 sec. cor. marked 1/4 on west face from which:
A pine 12" dia. bears S 32 W, 21 lks. dist. marked 1/4 S BT.
A fir 24" dia. bears N 04 E, 33 lks. dist. marked 1/4 S BT.



Description of corner evidence found:

At the assumed corner location I found a basalt stone 16" x 12" x 8" lying flush with the surface and with 1/4 marked on the west face, from which:
A pine stump approx. 20" dia. bears S 32 W, 21 lks. dist.; no blaze or scribing.
A badly rotted fir lying on the ground, base bears N 04 E, 33 lks. dist.; portions of scribing are visible.

Description of monument and accessories I established to perpetuate the original location of this corner:

As the evidence in the vicinity of the corner agrees with the GLO original record, at the location of the found stone, I set a 2 1/2" brass cap on a 30" galv. iron pipe, and being stamped as shown above, with a large mound of stone and dirt around the monument.

New bearing trees:

A fir 5" dia. bears N 85 W, 47.0 feet scribed 1/4 S S 17 BT.
A tamarack 9" dia. bears S 25 E, 46.5 feet scribed 1/4 S S 16 BT.

REGISTERED PROFESSIONAL LAND SURVEYOR

James H. Hambleton
8-21-78

OREGON
JULY 15, 1963
JAMES H. HAMBLETON
645

I hereby certify the above corner monument was re-established as herein described in August 1978.

Witnesses: *James H. Hambleton*
Crew Chief
P. D. Fisher
Instrument Man

L-9

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

93-39-B