


N-11

History of original corner establishment:

Corner was established in 1882, by Rufus S. Moore, under General Land Office Contract No. 451. Surveyor General's records state: Set a basalt stone 16 x 12 x 4, 11" in ground for $\frac{1}{4}$ sec. Cor. marked $\frac{1}{2}$ on N face from which:
 A fir 12" dia. bears N 43 W, 39 lks. dist. marked $\frac{1}{4}$ S BT.
 A fir 7" dia. bears S 12 E, 10 lks, dist. marked $\frac{1}{2}$ S BT.



Description of corner evidence found:

At assumed corner location I found a basalt stone 16 x 12 x 4 lying flat on the ground and marked $\frac{1}{2}$ on the side facing down with a small mound of stone alongside from which:
 A fir 22" dia. bears N 43 W, 39 lks. dist. with a portion of a healed blaze being opened at some previous time exposing a portion of the scribing; the tree is alive and in good condition.

A fir 15" dia. bears S 12 E, 10 lks. dist. with the blaze healed over completely.

Description of monument and accessories I established to perpetuate the original location of this corner:

As the evidence in the vicinity of the corner agrees with the GLO original record, at the location of the stone, I set a 2 $\frac{1}{2}$ " brass cap on a 30" galv. iron pipe, and being stamped as shown above, I placed the 16 x 12 x 4 basalt stone upside down in the hole along the west side of the monument and buried both in a large mound of stone and dirt.

I set no new bearing trees as it was not necessary.

I hereby certify the above corner monument was re-established as herein described in August 1978.

Witnesses: Leonard E. Green
Crew Chief
L. D. Shickles
Instrument Man

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
8-21-78

OREGON
JULY 10, 1963
JAMES H. HAMBLETON
645

N-11

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

93-39-B