

USDA-FOREST SERVICE


Index
 File No. N-11
 T 5 S R. 34 E
 Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. LaGrande County Union Tract or Survey No. _____
 N.F. WW-16 State Oregon Cor. No. 1

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

16" x 12" x 4" basalt stone lying flat on ground, mkd. $\frac{1}{4}$ on side face down with small mound of stone alongside.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

22" fir bears N 43 W, 39 lks. w/portion of healed blaze being opened at some previous time exposing portion of scribing. (old BT)
 15" fir bears S 12 E, 10 lks. w/blaze healed over completely. (old BT)

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Approx. 1600 ft. NE of road S536 on point of open ridge.

Signature
 Hambleton

Title

Division
 ORLS

Headquarters
 645

Date
 8-78

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" x 30" iron pipe w/brass cap mkd.:
Buried 16 x 12 x 4 basalt stone upside down
in hole along W side of monument. Both buried
in large mound of stone and dirt.

T 5 S
S 16
1/4 S 21
R 34 E
1978
ORLS 645

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted blaze and band on BT's red & yellow. Tagged trees w/54-3&4 signs.
Set steel fence post by mound of stone w/signs 54-5&6.

10

Work Done By J. Hambleton Title Surveyor Date 8-78 State Registration No. ORLS 645
or Agency
Certified Cor. Record Prepared? Yes No Filed At UNION CS Date

11

REMARKS

Witnesses: L. Green
L. Shirley

Index File No. T. R. M. Tract or Surv. No. Cor.

12

13