

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


N-5

History of original corner establishment:

Corner originally established by Rufus S Moore, U.S. Deputy Surveyor, under GLO Contract No. 451, dated June 12, 1882.

Surveyor General records state:

Set a post 4 ft long 4 ins sq. 24 ins in ground for cor. to secs. 17,18,19 & 20 marked T5SR34ES 17 on NE, T5SR34ES 18 on NW, S19 on SW and S20 on SE faces with 3 notches on S and 5 notches on East face from which:
 A tamarack 14 ins. in dia bears N12°E, 20 lks dist marked T5SR34ES17 BT.
 A pine 12 ins. in dia bears N43°W, 21 lks dist marked T5SR34ES18 BT.
 A tamarack 10 ins. in dia bears S57°W, 24 lks dist marked T5SR34ES19 BT.
 A tamarack 7 ins. in dia bears S35°E, 9 lks dist marked T5SR34ES20 BT.



Description of corner evidence found:

A 16" western larch stump bears N12°E, 20 lks (13.2') with blaze and axe marks visible... scribing burnt out.
 A stump hole bears S35°E, 9 lks (5.9') with pieces of rotted blaze alongside.

No trace of corner post in area of previous heavy logging.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by record bearing and distance from recovered remnants of Section 17 bearing tree...

Set a 2½" aluminum cap on 2½"x30" aluminum pipe 27" in ground surrounded with mound of earth & stone. Set a fence post of corner & attached sign 54-9 & 54-2.

New bearing trees established:

A 7½" diam. western larch brs. N12°E, 98.3' scribed T5SR34ES17 BT.
 A 9" diam. alpine fir brs S30°E, 51.8' scribed T5SR34ES20 BT.
 A 13½" diam. alpine fir brs S33°W, 76.4' scribed T5SR34ES19 BT.
 A 77" diam. alpine fir brs N68°W, 88.3' scribed T5SR34ES18 BT

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

Compass declination 18° East.

I hereby certify that the above corner was properly re-established to U.S.F.S. standards by me on October 26, 1993.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 12-31-94

Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

..... by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

Date 8-4-94

Rec'd By KK

No. 94-106-C