


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-5

History of original corner establishment:
Corner was originally established by Rufus S. Moore, U.S. Deputy Surveyor, under Contract No. 451, dated June 12, 1882. Surveyor General records state: Set a post 4 ft long 4 ins square 24 ins in the ground for the quarter corner to sections 19 and 20, from which:
A tamarack 7 ins. diam. bears N 88° W 50 lks. dist. marked: 1/4 S BT.
A tamarack 24 ins diam. bears S 37° E 20 lks. dist. marked: 1/4 S BT.



Description of corner evidence found:

Nothing found of original evidence. This corner was not re-established on this survey.

Corner area was searched on 2 separate occasions with a 2 person crew. Total search time was 4 1/2 hours. 2 hours of professional land surveyor time was include in the corner search effort. A 200 foot radius around the calculated corner area was searched.

This area has been heavily burnt 60 to 80 years ago. There are charred remains of several large stumps in the corner area, but no evidence of the original corner accessories.

Corner search area was determined by closed traverse control survey.

Description of monument and accessories | established to perpetuate the original location of this corner:

8-4-94
REGISTERED
PROFESSIONAL
LAND SURVEYOR
Will R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
renews 12-31-94

Office of County Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the day of 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor *GPO-591-971, 1988
Date 8-4-94
Rec'd By KK
No. 94-106-C
15