


R-13

History of original corner establishment:

Corner was established in 1882, by Rufus S. Moore, under General Land Office Contract No. 451. Surveyor General's record's state: Set a post 4 ft. long, 4" square, 24" in ground for cor. to Sec's. 21, 22, 27 & 28, marked T 5 S R 34 E S 22 on NE, T 5 S R 34 E S 21 on NW, S 28 on SW and S 27 on SE faces with 2 notches on S and 3 notches on E edges from which:



- A tamarack 9" dia. bears N 59 E, 8 lks. dist. marked T 5 S R 34 E S 22 BT.
- A tamarack 9" dia. bears N 43 W, 48 lks. dist. marked T 5 S R 34 E S 21 BT.
- A tamarack 11" dia. bears S 50 W, 9 lks. dist. marked T 5 S R 34 E S 28 BT.
- A fir 7" dia. bears S 54 E, 16 lks. dist. marked T 5 S R 34 E S 27 BT.

Description of corner evidence found:

At assumed corner location I found a 4 x 4 wood post leaning against a tree with visible scribing on two sides of the post from which:
A tamarack now 13" dia. alive and in good condition bears N 59 E, 8 lks. dist. with a blaze healed over.
A tamarack now 16" dia. alive and in good condition bears N 43 W, 48 lks. dist. with a blaze healed over.
A tamarack now 16" dia. alive and in good condition bears S 50 W, 9 lks. dist. with a blaze healed over.
A fir 12" dia. alive and in good condition bears S 54 E, 16 lks. dist. with a blaze partly healed over with scribing still visible.

Description of monument and accessories established to perpetuate the original location of this corner:

As the evidence in the vicinity of the corner agrees with the GLO original record, at the location reconstructed from the position of the original bearing trees, I set a 2 1/2" brass cap on a 30" galv. iron pipe and being stamped as shown above being with in 4" of the surface. There was no stone available in the area. I set no new bearing trees as it was not necessary.

I hereby certify the above corner monument was re-established as herein described in August 1978.

Witnesses: Leonard C. Brown Crew Chief
R. D. Fisher Instrument Man



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

89
93-39-B