

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/23/04

CORNER DESIGNATION: N-21, the Southeast Corner of Section 14, T6N., R33E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Deputy Surveyor, under Contract No. 209, dated July 6, 1874. Record states: Set alder post, 4 ft. long, 3 ins. sq. drove charred stake, raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 13, 14, 23 & 24. See below for addition survey references.

MONUMENT AND ACCESSORIES FOUND: None. Survey No. 96-07-B called for a Rock with "X", 1.0 foot North of fence corner. We dug a hole 3.5 feet deep by 4.5 feet wide and did not recover the called stone. I telephoned Ron Munns, who filed Survey No. 96-07-B and he did not remember the stone being particularly hard to find. I then reestablished the position of the stone with reference to ties made to Survey No. 96-07-B. See Sheet 1 of 2 of Kentch Partition for survey measurement data. The reestablished corner point falls about 2 West and 1.5 feet North of fence corner with fences extending South and about North 65° West. Survey No. C-014-C, by Stan Wallulis in 1966 shows a iron pin being set for "temporary section corner" near this location. We did not look for the iron pin because of it's indefinite nature.

MONUMENT MARKING DETAIL:

T6N R33E
S14 | S13
S23 | S24
2004
PLS 1106

MONUMENT SET: At position for corner described above, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe 26" int the ground.

New accessories to corner monument:

"XBO" chiseled into the top of a 24" x 12" x 6" above ground immovable granite rock, (an "erratic") bears N 26° E, 3.8 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 2" above ground level bears South, 22.3 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 2" above ground level bears S 02° W, 45.5 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with top 2" above ground level bears N 56° W, 35.2 feet.

Attached bearing object signs to all rebar accessories and attached witness sign to fence corner post Easterly of new corner monument.

LOCATION AND COMMENTS: Corner is located at a field and fence corner 1000 feet Southeast of Butler Grade Road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

6N33N21

RECEIVED BY
Umatilla County Surveyor
Date 4-04
Rec'd by KK
No. 04-73-B

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04