

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/17/01

CORNER DESIGNATION: P-11, Center 1/4 of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was established by Geary Kimbrell, Deputy County Surveyor, under Survey No. 239, dated March, 1906. Record states: "Set a stone for cen. of Sec. 21 on direct line with the 1/4 Sec. Corners both east and west and north and south".

MONUMENT AND ACCESSORIES FOUND: Found stone 12" x 10" x 8" with "x" marked on Southerly face.

MONUMENT MARKING DETAIL: Set rebar as described below.

MONUMENT SET:

At position of found stone, set a 5/8" x 30" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372". Placed original stone on North side of new monument with 4" exposed. From which:

A brass washer stamped "PLS 1106", 1 foot above ground, in fence post bears N 87° E, 80.0 feet.

"XBO" chiseled in large immovable rock at head of 2 way drainage which bears S 27 1/2° E, 94.6 feet.

5/8" rebar with yellow plastic cap monumenting the Center West 1/16th Corner of Section 21 bears N 89° 55' 58" W a distance of 1315.78 feet.

5/8" rebar with yellow plastic cap monumenting the Center South 1/16th Corner of Section 21 bears S 00° 00' 16" W a distance of 1352.67 feet.

Nailed bearing object tag on post with brass washer. Nailed "witness" sign to railroad tie fence corner which Southeast of corner.

LOCATION AND COMMENTS: Corner located at fence corner with fences East and South.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91): *Sti*
N: 850901.63
E: 8661148.16

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammerlsa
\\6N33P11

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor
Date 9-01
Rec'd By KE
No. 01-139-C

T&D R33