

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/17/01

CORNER DESIGNATION: R-11

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Records state: Set basalt stone, 15 x 12 x 10, 8 ins. in ground, for 1/4 Sec. Cor.

Geary Kimbrell, Deputy County Surveyor, recovered this corner during Survey No. 239, dated March, 1906, but does not state what was recovered.

MONUMENT AND ACCESSORIES FOUND: Found disturbed 14" x 10" x 8" stone with a slight visible 4, approximately 25 feet West from calculated position of corner—the area has been farmed and the corner uprooted.

MONUMENT MARKING DETAIL:

T6N R33E  
S21  
1/4-----  
S28  
2001  
PLS 1106

MONUMENT SET: Reestablished corner position by extending bearing and distance measured between recovered corners at the Center 1/4 and Center South 1/16th Corners of Section 21, Southerly from the Center South 1/16th Corner of Section 21. At position determined by survey, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe with top 18" below ground. Placed original corner stone on West side of new monument.

From which:

- A brass washer stamped "PLS 1106" in fence post bears South, 84.6 feet.
- A brass washer stamped "PLS 1106" in fence post bears S 26° E, 58.0 feet.
- A brass washer stamped "PLS 1106" in fence post bears S 65° E, 123.0 feet.
- 5/8" rebar monumenting the Center South 1/16th Corner of Section 21 bears N 00° 00' 16" E, 1352.67 feet.
- Attached bearing object tags to fence posts with brass washers.
- Set steel fence post with "witness" sign attached South of monument.
- (Used 1/16 Corner North for fourth accessory)

LOCATION AND COMMENTS:

Corner about 50 feet North of an old fence corner with fences extending South and East.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91): *fti*

N: 848196.99  
E: 8661205.32

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
V6N33R11

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

RECEIVED BY

Umatilla County Surveyor

Date 9-8-01

Rec'd By KK

No. 01-139-C