

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/29/09.

CORNER DESIGNATION: T-9, The West One-Quarter Corner of Section 28, Township 6 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Walden under GLO Contract No. 209, dated July 6, 1874. Notes state: Set basalt stone, 14 x 10 x 9, 7 ins. in ground, for 1/4 Sec. Cor.

MONUMENT AND ACCESSORIES FOUND: Found original set stone, marked 1/4 on West face.

MONUMENT MARKING DETAIL:

T6N R33E
S29 | S28
2009
PLS 1106

MONUMENT SET: At the position of the found original stone, set a 2 3/8" diameter brass cap monument on a 1 1/4" x 30" galvanized iron pipe, 22" in the ground, marked as shown in "Monument Marking Detail", and surrounded with earth and stone. Placed original stone in the new monument mound.

New accessories:

A silver Deep-1 magnet, bears North 36° East, a distance of 16.1 feet, buried 12 inches.

A 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", on 5/8" by 30" rebar, bears South 44° East, a distance of 18.2 feet.

A 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", on 5/8" by 30" rebar, bears South 25° West, a distance of 17.9 feet.

A orange Deep-1 magnet, bears North 50° West, a distance of 14.3 feet.

Rebar accessories have bearing object signs attached. Set steel fence post 3 feet North of corner with witness sign.

LOCATION AND COMMENTS: Corner located on a Southwest rocky slope.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 845566.52

E = 8658665.65

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Matt Brockamp
D. Palmer

\6N33T9



Will. R. Wells



renews 6-30-10

09-87-B