

OREGON CORNER RESTORATION FORM

Section: 19, 20, 29 & 30
Township: 6 North
Range: 35 East of the Willamette Meridian
County: Umatilla
Date: June 1, 2002

Corner Indexing Information: Township 6N Range 35E Corner Code R 5 (Willamette Meridian)

Additional Identifier: (e.g. BLM designation for the corner, street intersection, plat name, block, lot, etc.)

This corner is common to sections 19, 20, 29 & 30.

Oregon Plane Coordinates: N: 848570.326 E: 8716630.830

Zone: North **Order:** second **Datum:** NAD83-91 **Convergence:** 1°26'07.2" **Scale Factor:** .99995768

Previous Renewals/Surveys, etc.: Originally surveyed by U.S. Deputy Surveyor William Odell under his contract No. 110, dated 8-23-1865. The Surveyor General's notes state, "set post corner for sections 19, 20, 29, and 30, drove charred stake, dug pits, and raised mounds as per instructions." Survey No. 35, Book 1, Page 191, dated October 15, 1888, Arnold set a smooth boulder 18"x6"x5" at the location of the original post. Survey N-64-C, dated August 1977, McInd found a 1/2" bolt with a nut he held for road centerline only. Circa 1995, The Oregon Department of Transportation resurfaced the road and set a brass cap in a monument case.

Monument(s) & Accessories Found (Condition & Source):

At the Southwest corner of section 20, T6N R35E, we found 3" brass cap in 5" diameter iron monument case 2 1/2" below the surface pavement.

Monument Set (Procedures & Description):

Monument Detail:



New Accessories: WE SET:

A 5/8 rebar with yellow plastic cap stamped 'Tomkins Surveying' which bears N 40°E ~ 29.41 feet from the corner. No Umatilla County Bearing object sign or t-post set. A 5/8 rebar with yellow plastic cap stamped 'Tomkins Surveying' which bears S 50°E ~ 29.59 feet from the corner. No Umatilla County Bearing object sign or t-post set. A 5/8 rebar with yellow plastic cap stamped 'Tomkins Surveying' which bears S 40°W ~ 18.57 feet from the corner. No Umatilla County Bearing object sign or t-post set. A 5/8 rebar with yellow plastic cap stamped 'Tomkins Surveying' which bears N 50°W ~ 42.11 feet from the corner. Attached a Umatilla County Bearing object to the south face of a railroad tie post.

Location & Comments:

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.
 20 E. Poplar, Suite 204
 Walla Walla, WA 99362

Party Chief: Bryan Martin
Notes: Bryan Martin
Witness: Eric Flowers

Surveyor's Seal



renews 6/30/04
6/30/02