

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/28/2014

CORNER DESIGNATION: J/K25 and J/K-1

Closing corner J/K-25 S13T6NR37E and J/K-1 S18T6NR38E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis in 1865 they set a post 15.80 chains West of the 41 mile post from which a tamarack tree 10" in diam. bears S 70° E., 9 links dist. and a fir tree 8" in diam. bears S 50° W., 40 links dist.

In 1991 BLM Cadastral Surveyor Richard L. Johnson re-surveyed the range line between R37E and R38E and set a stainless steel post in a mound of stone at the true closing corner no evidence of the original corner remained. From which a Ponderosa Pine 20" in diam. bears S 54½ °E. 114 links distance marked T6N R38ES18 CCBT. A fir tree 16" in diam. bears S 63° W 260 links marked T6N R337ES13 CCBT

MOUNUMENT AND ACCESSORIES FOUND:

Found BLM 3 ¼ inch brass cap on 2 ½ inch stainless steel post projecting 1.1 feet above ground with mound of stones on Northerly side of monument (uphill.)

Found 1 inch square iron rod, reestablished by Wayne Harris as the closing corner in 1960 at N 1½° W, 30.10 ft., per CS 03-291-A.

Found 28" diam. Ponderosa Pine bearing S 57° E., 75.3 feet marked T6NR38ES18BT.

Found 16" diam. fir bearing S 63° W., 171.6 feet marked T6NR37ES13 CCBT

MOUNUMENT MARKING DETAIL:

T6N
R37E
WASH

ORE |
S13 | S18
CC
R37E R38E
T6N
1991

MOUNUMENT AND ACCESSORIES SET:

Set ½ inch iron rebar with red cap marked "TLS/HDJ" Bearing S 2° W., 33 ft. projecting 0.6 ft. attached sign marked: T6NR37ES13BO

Set ½ inch rebar with red cap marked "TLS/HDJ" attached sign marked T6NR37ES13BO

LOCATION AND COMMENTS:

Corner is located on a steep south facing slope approximately 125 ft. to the bottom of the valley and a small creek. The 41 mile post on the Oregon and Washington border bears N 89°55'48" E., 1007.73 ft. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 859813.01

E = 8806065.71


COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Felipe G. Hernandez

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015