


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. A-7

History of original corner establishment:

In 1872, under G.L.O. Contract No. 176, George Williams set a post and marked stone in a mound of earth for 1/4 Sec. Cor.



Description of corner evidence found:

A diligent search was made and no evidence of stone could be found.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set at proportioned point a 1"x30" Galvanized Pipe with 3" brass cap stamped:


Set pipe 24" in ground with mound of stone to cap.

Bearing Trees:

A Ponderosa Pine 6" dia. bears S29°E 55.0 ft., scribed: 1/4 S5 BT.

A Douglas Fir 15" dia. bears S64°W 62.9 ft., scribed: 1/4 S5 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washers to foot blaze of both BTs. Stamped LS 1294. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was reestablished as herein described on October 10, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wyatt
A. Hanley

Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of..... December....., 19..... 80
..... David A. Hummel..... by..... Betty Shatt.....
(COUNTY OFFICIAL) (DEPUTY)