


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Meldrum & Campbell under General Land Office Contract No. 380.

Surveyor General Record States:

Set post for closing cor. to sects. 35 & 36. From which:

- A 18" Pine bears N 18 W, 132 lks.
- A 40" Pine bears S 18 W, 21 lks.
- A 12" Pine bears S 77 E, 132 lks.



No record of subsequent remonumentation was found in County Records.
Description of corner evidence found:

Found mound of stone, from which:

Original BTs.

- A 19" Pine, good condition, bears S83E, 87.1 ft., scribes visable.
- A 38" Pine stump bears S18+W, 14+ ft., scribes visable. (Tree was up rooted).
- A 20" Pine, good condition, bears N5W, 87.1 ft., scribes visable.


Description of monument and accessories established to perpetuate the original location of this corner

At corner point, based on BTs, I set 2 1/2"x30" iron pipe 24" in ground, from which:

New BTs:

A 15" Pine bears S72W, 57.2 ft. marked T6S R29E S1 CC BT.

- Nailed brass washer in BT blaze.
- Raised mound of stone 5 ft. at base to top of cap.
- Set steel fence post 5+ ft. South of corner.
- Used steel tape and magnetic compass with 20° E declination.
- Measured to face of blaze on original BTs and center of new BTs.



Office of Surveyor County of Umatilla

State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 13 day of Aug 1974.

Ralph Thompson by _____ (DEPUTY)

(COUNTY OFFICIAL)

A-1