

USDA-FOREST SERVICE

Index

File No. A-13

TSS

R30E

Merid. Willamette

R.D.
N.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County: Umatilla

State Oregon

Cor.

No.

x

Corner Diagram TSSR30E
533
54 | S3
T6S | R30E
CC
1976

x OPLS 598

1

1 Describe corner monument found
1 Steel pipe extending 15" above the ground with a 2 1/2" brass cap stamped as
1 shown in the diagram. Monument is in a stone mound.
1
1
1
1

1

x

Photo Identification Data

Photo No.

filed at

Object Ident.

Ident. by

Signature

x
1 Describe bearing trees or other official accessories found
1 A dead and down Lodgepole Pine bears N36°W, 13.0' scribed TSS in a weathered
1 blaze. A 24" Ponderosa Pine stump bears S18°E, 36.0' scribed E3.
1 A 10" Douglas Fir bears S61°E, 74.4' with healed scribe.
1 A 15" Ponderosa Pine bears S31°W, 52.2' with healed scribe.
1

1

x

Plane Coordinate Position Data

State

Zone

x

y

Estab. by

Agency

x
1 Describe corner location relative to near-by features, also how to reach corner
1 From the junction of roads 5312 and 5320, follow road 5320 east 0.5 miles to
1 road 5320100. Follow road 5320100 south 0.6 miles to an east-west fence line.
1 Follow this fence line east approximately 0.3 miles. The corner is located
1 approximately 50' north of this fence line.
1

1

x

Signature Title Division Headquarters Date
David L. Hadlock Land Surveyor Pendleton, OR June 1988

7100.52

CORNER RECORD (PERPETUATION)

X-----X

Monument: Describe new monument set, or work done to preserve existing monument

Set 30" aluminum pipe 17" in the ground at the intersection of the First Standard Parallel and the section line from the south. Stamped the 2 1/2" aluminum cap as shown in the diagram to the right. Built a stone mound around the monument. The new monument is about 2.20' north of the amended monument. Set a steel fence post 5' east of the monument and attached Forest Service Land Survey Monument and Property Boundary signs. Stamped the brass cap by OPLS 598 "AM".

T5SR30E
 S33
 S4 | S3
 T6S | R30E
 CC
 PLS 852

x-----x

Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Used old bearing trees as bearing trees for the new monument. These trees are located as follows with respect to the new monument. The 10" Douglas Fir bears S57°15'E, 75.6'. The 15" Ponderosa Pine bears S31°00'W, 54.1'. Attached Forest Service Land Survey Monument and Bearing Tree signs to these trees and repainted red bands and blazes on all of the trees.

x-----x

Work done by	David L. Haddock	Title	Land Surveyor	Date	Nov 1988	State Registration No.	
Certified cor. record prepared?	yes x		no	Filed at	Pendleton, OR	or Agency	852
				Date	Dec 1988		
					Jan. 1989		

REMARKS

x-----x

Index File No.	A-13	T.6S.	R.30E.	M. Willamette	Tract or Survey No	Cor.
----------------	------	-------	--------	---------------	--------------------	------

USDA-FOREST SERVICE

Index File No. A-13

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. CC


T T6S R. R30E

R.D. UKIAH County UMATILLA

Merid. WILLAMETTE

N.F. UMATILLA State OR

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

FD. BASALT STONE 15"x8"x7" MKD CC + with notches SET IN HD OF STONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

COR IS 32 FT NORTH OF E-W. FENCELINE

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
R. W. Baggett

Title
LAND SURVEYOR

Division

Headquarters

Date
9-30-76

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

SET 2 1/2" x 30" IRON PIPE w/ BRASS CAP MKD.

T5SR30E

S33	
S4	S3
T6S	CC R30E
1976	
OPL5598	

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

NEW BT'S

A 10" FIR BRS. S61°E. 74 1/2 FT. MKD T6SR30E S3CC BT.

A 15" FIR BRS S31°W. 52 1/2 FT. MKD T6SR30E S4CC BT.

10

Work Done By: R.D. Boggett Title Land Surveyor Date 9-20-76 State Registration No. OPL5598
or AgencyCertified Cor. Record Prepared? Yes No Filed At: UMATILLA C.S. Date

11

REMARKS

12

Index File No. A-13 T. R. M. Tract or Surv. No. Cor.

13